



CE&UKCA EMC Test Report

Project No. : 2409C069D
Equipment : LCD Monitor
Brand Name : N/A
Model Name : 25G4S
Series Model : **25G4*****, **CS25***** (*=0-9,A-Z,a-z,+, -, \ or blank), 25G4SRE, 25G4K
Applicant : TPV Electronics (Fujian) Co., Ltd.
Address : Rongqiao Economic and Technological Development Zone, Fuqing City, Fujian Province, P.R. China
Date of Receipt : Apr. 08, 2025
Date of Test : Apr. 10, 2025 ~ May 06, 2025
Issued Date : May 12, 2025
Report Version : R00
Test Sample : Engineering Sample No.: DG2025040864
Standard(s) : Please refer to Page 2.

The above equipment has been tested and found compliance with the requirement of the relative standards by BTL Inc. (Dongguan)

Prepared by : Jeter Wang

Jeter Wang

Approved by : Kang Zhang

Kang Zhang

No.3, Jinshagang 1st Road, Dalang, Dongguan, Guangdong People's Republic of China.

Tel: +86-769-8318-3000 Web: www.newbtl.com Service mail: btl_qa@newbtl.com

Standard(s)	:	EN 55032:2015 EN 55032:2015+A11:2020 EN 55032:2015+A1:2020 CISPR 32:2015+AMD1:2019 AS/NZS CISPR 32:2015+AMD1:2020 EN 61000-3-2:2014 EN IEC 61000-3-2:2019+A1:2021 EN 61000-3-3:2013 EN 61000-3-3:2013+A1:2019 EN 61000-3-3:2013+A2:2021 EN 55035:2017/CISPR 35:2016 EN 55035:2017+A11:2020
		BS EN 55032:2015 BS EN 55032:2015+A11:2020 BS EN 55032:2015+A1:2020 BS EN 61000-3-2:2014 BS EN IEC 61000-3-2:2019+A1:2021 BS EN 61000-3-3:2013 BS EN 61000-3-3:2013+A1:2019 BS EN 61000-3-3:2013+A2:2021 BS EN 55035:2017 BS EN 55035:2017+A11:2020

Declaration

BTL represents to the client that testing is done in accordance with standard procedures as applicable and that test instruments used has been calibrated with standards traceable to international standard(s) and/or national standard(s).

BTL's reports apply only to the specific samples tested under conditions. It is manufacturer's responsibility to ensure that additional production units of this model are manufactured with the identical electrical and mechanical components. **BTL** assumes no responsibility for the data provided by the customer, any statements, inferences or generalizations drawn by the customer or others from the reports issued by **BTL**.

The report must not be used by the client to claim product certification, approval, or endorsement by A2LA or any agency of the U.S. Government.

This report is the confidential property of the client. As a mutual protection to the clients, the public and ourselves, the test report shall not be reproduced, except in full, without our written approval.

BTL's laboratory quality assurance procedures are in compliance with the ISO/IEC 17025: 2017 requirements, and accredited by the conformity assessment authorities listed in this test report.

BTL is not responsible for the sampling stage, so the results only apply to the sample as received.

The information, data and test plan are provided by manufacturer which may affect the validity of results, so it is manufacturer's responsibility to ensure that the apparatus meets the essential requirements of applied standards and in all the possible configurations as representative of its intended use.

Limitation

For the use of the authority's logo is limited unless the Test Standard(s)/Scope(s)/Item(s) mentioned in this test report is (are) included in the conformity assessment authorities acceptance respective.

Please note that the measurement uncertainty is provided for informational purpose only and are not use in determining the Pass/Fail results.

Table of Contents	Page
REPORT ISSUED HISTORY	7
1 . SUMMARY OF TEST RESULTS	8
1.1 TEST FACILITY	10
1.2 MEASUREMENT UNCERTAINTY	10
1.3 TEST ENVIRONMENT CONDITIONS	11
2 . GENERAL INFORMATION	12
2.1 GENERAL DESCRIPTION OF EUT	12
2.2 DESCRIPTION OF TEST MODES	13
2.3 EUT OPERATING CONDITIONS	15
2.4 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED	15
2.5 DESCRIPTION OF SUPPORT UNITS	15
3 . EMC EMISSION TEST	16
3.1 RADIATED EMISSIONS UP TO 1 GHZ	16
3.1.1 LIMITS	16
3.1.2 MEASUREMENT INSTRUMENTS LIST	16
3.1.3 TEST PROCEDURE	17
3.1.4 DEVIATION FROM TEST STANDARD	17
3.1.5 TEST SETUP	17
3.1.6 MEASUREMENT DISTANCE	18
3.1.7 TEST RESULTS	19
3.2 RADIATED EMISSIONS ABOVE 1 GHZ	23
3.2.1 LIMITS	23
3.2.2 MEASUREMENT INSTRUMENTS LIST	23
3.2.3 TEST PROCEDURE	24
3.2.4 DEVIATION FROM TEST STANDARD	24
3.2.5 TEST SETUP	24
3.2.6 MEASUREMENT DISTANCE	25
3.2.7 TEST RESULTS	26
3.3 CONDUCTED EMISSION MEASUREMENT AT AC MAINS POWER PORTS	30
3.3.1 LIMITS	30
3.3.2 MEASUREMENT INSTRUMENTS LIST	30
3.3.3 TEST PROCEDURE	30
3.3.4 DEVIATION FROM TEST STANDARD	30
3.3.5 TEST SETUP	31
3.3.6 TEST RESULTS	32
3.4 HARMONIC CURRENT EMISSIONS TEST	36
3.4.1 LIMITS	36
3.4.2 MEASUREMENT INSTRUMENTS LIST	36
3.4.3 TEST PROCEDURE	36

Table of Contents

	Page
3.4.4 DEVIATION FROM TEST STANDARD	36
3.4.5 TEST SETUP	36
3.4.6 TEST RESULTS	37
3.5 VOLTAGE FLUCTUATIONS (FLICKER) TEST	40
3.5.1 LIMITS	40
3.5.2 MEASUREMENT INSTRUMENTS LIST	40
3.5.3 TEST PROCEDURE	40
3.5.4 DEVIATION FROM TEST STANDARD	40
3.5.5 TEST SETUP	41
3.5.6 TEST RESULTS	42
4 . EMC IMMUNITY TEST	43
4.1 STANDARD COMPLIANCE/SEVERITY LEVEL/CRITERIA	43
4.2 GENERAL PERFORMANCE CRITERIA	46
4.3 ANNEX D (NORMATIVE) - DISPLAY AND DISPLAY OUTPUT FUNCTION	47
4.3.1 PERFORMANCE CRITERIA	47
4.4 ANNEX G (NORMATIVE) - AUDIO OUTPUT FUNCTION	48
4.4.1 PERFORMANCE CRITERIA	48
4.5 ELECTROSTATIC DISCHARGE IMMUNITY TEST (ESD)	49
4.5.1 TEST SPECIFICATION	49
4.5.2 MEASUREMENT INSTRUMENTS	49
4.5.3 TEST PROCEDURE	49
4.5.4 DEVIATION FROM TEST STANDARD	50
4.5.5 TEST SETUP	50
4.5.6 TEST RESULTS	51
4.6 RADIATED, RADIO-FREQUENCY, ELECTROMAGNETIC FIELD IMMUNITY TEST (RS)	54
4.6.1 TEST SPECIFICATION	54
4.6.2 MEASUREMENT INSTRUMENTS	54
4.6.3 TEST PROCEDURE	54
4.6.4 DEVIATION FROM TEST STANDARD	55
4.6.5 TEST SETUP	55
4.6.6 TEST RESULTS	57
4.7 ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST (EFT)	60
4.7.1 TEST SPECIFICATION	60
4.7.2 MEASUREMENT INSTRUMENTS	60
4.7.3 TEST PROCEDURE	60
4.7.4 DEVIATION FROM TEST STANDARD	60
4.7.5 TEST SETUP	61
4.7.6 TEST RESULTS	62
4.8 SURGE IMMUNITY TEST (SURGE)	63
4.8.1 TEST SPECIFICATION	63
4.8.2 MEASUREMENT INSTRUMENTS	63
4.8.3 TEST PROCEDURE	63

Table of Contents

	Page
4.8.4 DEVIATION FROM TEST STANDARD	63
4.8.5 TEST SETUP	64
4.8.6 TEST RESULTS	65
4.9 IMMUNITY TO CONDUCTED DISTURBANCES, INDUCED BY RADIO-FREQUENCY	
FIELDS TEST (CS)	66
4.9.1 TEST SPECIFICATION	66
4.9.2 MEASUREMENT INSTRUMENTS	66
4.9.3 TEST PROCEDURE	66
4.9.4 DEVIATION FROM TEST STANDARD	67
4.9.5 TEST SETUP	67
4.9.6 TEST RESULTS	69
4.10 POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST (PFMF)	71
4.10.1 TEST SPECIFICATION	71
4.10.2 MEASUREMENT INSTRUMENTS	71
4.10.3 TEST PROCEDURE	71
4.10.4 DEVIATION FROM TEST STANDARD	71
4.10.5 TEST SETUP	72
4.10.6 TEST RESULTS	73
4.11 VOLTAGE DIPS, SHORT INTERRUPTIONS AND VOLTAGE VARIATIONS IMMUNITY	
TEST (DIPS)	74
4.11.1 TEST SPECIFICATION	74
4.11.2 MEASUREMENT INSTRUMENTS	74
4.11.3 TEST PROCEDURE	74
4.11.4 DEVIATION FROM TEST STANDARD	74
4.11.5 TEST SETUP	74
4.11.6 TEST RESULTS	75
5 . EUT TEST PHOTO	76

REPORT ISSUED HISTORY

Report No.	Version	Description	Issued Date	Note
BTL-EMC-1-2409C069D	R00	<p>This is a supplementary report to the original test report (BTL-EMC-1-2409C069C).</p> <p>1. Added the series model.</p> <p>2. Updated the highest internal frequency (Fx).</p> <p>3. Updated the refresh rate of DP port.</p> <p>4. Added the new mainboard.</p> <p>So the EMI items tested the worst mode of original report, the EMS items tested all modes and recorded. The original test results please refer to original report.</p>	May 12, 2025	Valid

1. SUMMARY OF TEST RESULTS

Test procedures according to the technical standards:

Emission		
Standard(s)	Test Item	Result
EN 55032:2015 EN 55032:2015+A11:2020 EN 55032:2015+A1:2020 CISPR 32:2015+AMD1:2019 AS/NZS CISPR 32:2015+AMD1:2020 BS EN 55032:2015 BS EN 55032:2015+A11:2020 BS EN 55032:2015+A1:2020	Radiated emissions up to 1 GHz	PASS
	Radiated emissions above 1 GHz	PASS
	Radiated emissions from FM receivers	N/A
	Conducted emissions AC mains power port	PASS
	Asymmetric mode	AAN
	conducted emissions	N/A
	Current Probe	N/A
	CP+CVP	N/A
Conducted differential voltage emissions		N/A

Standard(s)	Test Item	Result
EN 61000-3-2:2014 EN IEC 61000-3-2:2019+A1:2021 BS EN 61000-3-2:2014 BS EN IEC 61000-3-2:2019+A1:2021	Harmonic current	PASS
EN 61000-3-3:2013 EN 61000-3-3:2013+A1:2019 EN 61000-3-3:2013+A2:2021 BS EN 61000-3-3:2013 BS EN 61000-3-3:2013+A1:2019 BS EN 61000-3-3:2013+A2:2021	Voltage fluctuations (Flicker)	PASS

Immunity			
Standard(s)	Ref Standard(s)	Test Item	Result
EN 55035:2017/CISPR 35:2016 EN 55035:2017+A11:2020 BS EN 55035:2017 BS EN 55035:2017+A11:2020	IEC 61000-4-2:2008 EN 61000-4-2:2009	ESD	PASS
	IEC 61000-4-3:2020 EN IEC 61000-4-3:2020	RS	PASS
	IEC 61000-4-4:2012 EN 61000-4-4:2012	EFT	PASS
	IEC 61000-4-5:2014+AMD1:2017 EN 61000-4-5:2014+A1:2017	Surge	PASS
	IEC 61000-4-6:2013 EN 61000-4-6:2014+AC:2015	CS	PASS
	IEC 61000-4-8:2009 EN 61000-4-8:2010	PFMF	PASS
	IEC 61000-4-11:2020 EN IEC 61000-4-11:2020	Dips	PASS

Standard(s)	Section	Test Item	Result
EN 55035:2017/CISPR 35:2016 EN 55035:2017+A11:2020 BS EN 55035:2017 BS EN 55035:2017+A11:2020	4.2.7	BIN-R	N/A
	4.2.7	BIN-I	N/A

NOTE:

- (1) "N/A" denotes test is not applicable to this device.
- (2) This supplementary report does not affect the standards: EN 55032:2015 & BS EN 55032:2015, the test results please refer to the original report: BTL-EMC-1-2409C069B.

1.1 TEST FACILITY

The test facilities used to collect the test data in this report No.3, Jinshagang 1st Road, Dalang, Dongguan, Guangdong People's Republic of China.

1.2 MEASUREMENT UNCERTAINTY

Where relevant, the following measurement uncertainty levels have been estimated for tests performed on the EUT as specified in CISPR 16-4-2, The BTL measurement uncertainty is less than the CISPR 16-4-2 $U_{\text{cisp}}^{\text{r}}$ requirement.

The reported uncertainty of measurement $y \pm U$, where expanded uncertainty U is based on a standard uncertainty multiplied by a coverage factor of $k=2$, providing a level of confidence of approximately 95%.

A. Radiated emissions up to 1 GHz measurement:

Test Site	Method	Measurement Frequency Range	Ant. H / V	U ,(dB)
DG-CB08 (10m)	CISPR	30MHz ~ 200MHz	V	4.48
		30MHz ~ 200MHz	H	4.50
		200MHz ~ 1,000MHz	V	4.60
		200MHz ~ 1,000MHz	H	4.84

B. Radiated emissions above 1 GHz measurement:

Test Site	Method	Measurement Frequency Range	U ,(dB)
DG-CB08 (3m)	CISPR	1GHz ~ 6GHz	4.24

C. Conducted emissions AC mains power port measurement:

Test Site	Method	Measurement Frequency Range	U ,(dB)
DG-C01	CISPR	150kHz ~ 30MHz	2.98

D. Harmonic current / Voltage fluctuations (Flicker) measurement:

Test Site	Method	Item	U (%)
DG-C01	EN 61000-3-2 EN 61000-3-3	Current	0.757
		Voltage	0.592

Note: Unless specifically mentioned, the uncertainty of measurement has not been taken into account to declare the compliance or non-compliance to the specification.

1.3 TEST ENVIRONMENT CONDITIONS

Test Item	Temperature	Humidity	Tested By	Test Date
Radiated emissions up to 1 GHz	21°C	52%	Carrey Wang	Apr. 24, 2025
Radiated emissions above 1 GHz	21°C	52%	Carrey Wang	Apr. 24, 2025
Conducted emissions AC mains power port	24°C	54%	Tansy Yan	Apr. 24, 2025
Harmonic current	26°C	56%	Cedric Chen	Apr. 24, 2025
Voltage fluctuations (Flicker)	26°C	56%	Cedric Chen	Apr. 24, 2025

Test Item	Temperature	Humidity	Pressure	Tested By	Test Date
ESD	26°C	50%	1013hPa	Niko Ning	Apr. 22, 2025
RS	20°C	55%	/	Hunter Xu	May 01, 2025
	20°C	50%	/	Hunter Xu	May 02, 2025
EFT	28°C	51%	/	Sean Wan	May 06, 2025
Surge	28°C	51%	/	Sean Wan	May 06, 2025
CS	25°C	55%	/	Promise Yin	May 04, 2025
PFMF	28°C	51%	/	Sean Wan	May 06, 2025
Dips	22°C	58%	/	Ellery Liang	May 01, 2025

2. GENERAL INFORMATION

2.1 GENERAL DESCRIPTION OF EUT

Equipment	LCD Monitor
Brand Name	N/A
Model Name	25G4S
Series Model	**25G4*****, **CS25***** (*=0-9,A-Z,a-z,+, -, / or blank), 25G4SRE, 25G4K
Model Difference(s)	Only differ in model name due to marketing purpose.
Identification No. of EUT(S/N)	N/A
Component unit of EUT	<input checked="" type="checkbox"/> Single unit <input type="checkbox"/> Multiple unit
Sample Status	<input checked="" type="checkbox"/> Engineering sample <input type="checkbox"/> Final shipment prototype
Power Source	AC Mains.
Power Rating	100-240V~ 50/60Hz 1.5A
Connecting I/O Port(s)	1* AC port 2* HDMI port 1* DP port 1* Earphone port
Classification of EUT	Class B
Highest Internal Frequency(Fx)	988.73MHz

Cable Type	Shielded Type	Ferrite Core	Length(m)	Note
AC Power Cord	Non-shielded	NO	1.8/1.5/1.2	-
HDMI	Shielded	YES	1.8/1.5/1.2	Bonded two Ferrite Cores
DP	Shielded	NO	1.8/1.5/1.2	-

Note:

1. For a more detailed features description, please refer to the manufacturer's specifications or the user's manual.

2.2 DESCRIPTION OF TEST MODES

To investigate the maximum EMI emission characteristics generates from EUT, the test system was pre-scanning tested base on the consideration of following EUT operation mode or test configuration mode which possible have effect on EMI emission level. Each of these EUT operation mode(s) or test configuration mode(s) mentioned above was evaluated respectively.

Pretest Mode	Description
Mode 1	HDMI1 1920*1080/240Hz PC 1.8m
Mode 2	HDMI2 1920*1080/240Hz PC 1.8m
Mode 3	DP 1920*1080/420Hz PC 1.8m
Mode 4	HDMI1 1080P DVD 1.8m
Mode 5	HDMI1 1920*1080/240Hz PC 1.5m
Mode 6	HDMI2 1920*1080/240Hz PC 1.5m
Mode 7	DP 1920*1080/420Hz PC 1.5m
Mode 8	HDMI1 1920*1080/240Hz PC 1.2m
Mode 9	HDMI2 1920*1080/240Hz PC PC 1.2m
Mode 10	DP 1920*1080/420Hz PC 1.2m

Radiated emissions up to 1 GHz Test	
Final Test Mode	Description
Mode 1	HDMI1 1920*1080/240Hz PC 1.8m

Radiated emissions Above 1 GHz Test	
Final Test Mode	Description
Mode 1	HDMI1 1920*1080/240Hz PC 1.8m

Conducted emissions AC mains power port Test	
Final Test Mode	Description
Mode 1	HDMI1 1920*1080/240Hz PC 1.8m

Harmonic current & Voltage fluctuations(Flicker) Test	
Final Test Mode	Description
Mode 1	HDMI1 1920*1080/240Hz PC 1.8m

Immunity Test	
Final Test Mode	Description
Mode 1	HDMI1 1920*1080/240Hz PC 1.8m
Mode 2	HDMI2 1920*1080/240Hz PC 1.8m
Mode 3	DP 1920*1080/420Hz PC 1.8m
Mode 4	HDMI1 1080P DVD 1.8m
Mode 5	HDMI1 1920*1080/240Hz PC 1.5m
Mode 6	HDMI2 1920*1080/240Hz PC 1.5m
Mode 7	DP 1920*1080/420Hz PC 1.5m
Mode 8	HDMI1 1920*1080/240Hz PC 1.2m
Mode 9	HDMI2 1920*1080/240Hz PC PC 1.2m
Mode 10	DP 1920*1080/420Hz PC 1.2m

Note:


1. RS: The Front, Rear, Left and Right were evaluated. The worst placement direction is Front and recorded in this report.
2. The audio output function of CS/RS is recorded the worst mode.

2.3 EUT OPERATING CONDITIONS

The EUT exercise program used during radiated and/or conducted emission measurement was designed to exercise the various system components in a manner similar to a typical use. The standard test signals and output signal as following:

1. EUT connected to Earphone via Earphone Cable.
2. EUT connected to PC via HDMI & DP Cable.
3. Mouse and Keyboard connected to PC via USB Cable.

2.4 BLOCK DIAGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED



2.5 DESCRIPTION OF SUPPORT UNITS

The EUT has been tested as an independent unit together with other necessary accessories or support units. The following support units or accessories were used to form a representative test configuration during the tests.

Item	Equipment	Mfr/Brand	Model/Type No.	Series No.
A	Earphone	Apple	N/A	N/A
B	PC	DELL	8920-D16N8S	GZS91L2
C	Keyboard	DELL	KB212-B	CN0HTXH97158125004DXA01
D	Mouse	DELL	MS111-P	CN011D3V71581279OLOT

Item	Cable Type	Shielded Type	Ferrite Core	Length
1	AC Cable	NO	NO	1.8/1.5/1.2m
2	Earphone Cable	NO	NO	1.2m
3	HDMI Cable	YES	YES	1.8/1.5/1.2m
4	HDMI Cable	YES	YES	1.8/1.5/1.2m
5	DP Cable	YES	NO	1.8/1.5/1.2m
6	USB Cable	YES	NO	1.8m
7	USB Cable	YES	NO	1.8m

3. EMC EMISSION TEST

3.1 RADIATED EMISSIONS UP TO 1 GHZ

3.1.1 LIMITS

Class B equipment up to 1 GHz

Frequency Range MHz	Measurement			Class B limits dB(μV/m)
	Facility	Distance m	Detector type/ bandwidth	
30 - 230	SAC	10	Quasi peak / 120 kHz	30
230 - 1000				37

Notes:

- (1) The limit for radiated test was performed according to as following: EN 55032
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dB_uV/m)=20log Emission level (uV/m).
- (4) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Antenna Factor + Cable Loss - Amplifier Gain(if use)

Margin Level = Measurement Value - Limit Value

3.1.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Receiver	Keysight	N9038A	MY54450004	Jun. 01, 2025
2	MXE EMI Receiver	Agilent	N9038A	MY53220133	Jun. 01, 2025
3	Pre-Amplifier	EMC INSTRUMENT	EMC 9135	980284	May 31, 2025
4	Pre-Amplifier	EMC INSTRUMENT	EMC 9135	980283	May 31, 2025
5	Trilog-Broadband Antenna	Schwarzbeck	VULB9168	947	Nov. 06, 2025
6	Attenuator	EMCI	EMCI-N-6-06	AT-N0670	Nov. 06, 2025
7	Trilog-Broadband Antenna	Schwarzbeck	VULB9168	1461	Nov. 27, 2025
8	Attenuator	EMC INSTRUMENT	EMCI-N-6-06	AT-06010	Nov. 27, 2025
9	Measurement Software	Farad	EZ-EMC Ver.BTL-2ANT-1	N/A	N/A
10	Multi-Device Controller	ETS-Lindgren	2090	N/A	N/A
11	Controller	MF	MF-7802	MF780208159	N/A
12	Cable	RW	LMR400-NMNM-10M	N/A	Dec. 01, 2025
13	Cable	RW	LMR400-NMNM-7M	N/A	Dec. 01, 2025
14	Cable	RW	LMR400-NMNM-3.5M	N/A	Dec. 01, 2025
15	Cable	RW	LMR400-NMNM-8M	N/A	Apr. 02, 2026
16	Cable	RW	LMR400-NMNM-3.5M	N/A	Apr. 02, 2026
17	Cable	RW	LMR400-NMNM-14M	N/A	Apr. 02, 2026

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.

All calibration period of equipment list is one year.


3.1.3 TEST PROCEDURE

- a. The measuring distance of 10 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 10 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.
- b. The height of the equipment or of the substitution antenna shall be 0.8 m, the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- c. The initial step in collecting radiated emission data is a receiver peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
- d. All readings are Peak unless otherwise stated QP in column of Note. Peak denotes that the Peak reading compliance with the QP Limits and then QP Mode measurement didn't perform.
- e. For the actual test configuration, please refer to the related Item - EUT Test Photos.

3.1.4 DEVIATION FROM TEST STANDARD

No deviation

3.1.5 TEST SETUP



3.1.6 MEASUREMENT DISTANCE




Figure C.1 – Measurement distance





Figure C.2 – Boundary of EUT, Local AE and associated cabling


3.1.7 TEST RESULTS

Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Mode 1		




No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comment
1		32.9100	41.55	-19.49	22.06	30.00	-7.94	QP	
2		107.6000	41.48	-20.51	20.97	30.00	-9.03	QP	
3	*	142.5200	42.76	-16.91	25.85	30.00	-4.15	QP	
4		177.4400	39.29	-16.97	22.32	30.00	-7.68	QP	
5		427.7000	37.56	-11.81	25.75	37.00	-11.25	QP	
6		764.2900	37.34	-7.19	30.15	37.00	-6.85	QP	

Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Mode 1		




No.	Mk.	Freq.	Reading	Correct	Measure-	Limit	Margin	Detector	Comment
			Level	Factor	ment				
1		180.3500	41.15	-18.57	22.58	30.00	-7.42	QP	
2	*	427.7000	44.86	-12.43	32.43	37.00	-4.57	QP	
3		509.1800	38.88	-10.96	27.92	37.00	-9.08	QP	
4		713.8500	38.88	-8.26	30.62	37.00	-6.38	QP	
5	!	774.9600	39.87	-7.59	32.28	37.00	-4.72	QP	
6	!	824.4300	39.13	-7.47	31.66	37.00	-5.34	QP	

Test Voltage	AC 110V/60Hz	Polarization	Vertical
Test Mode	Mode 1		



No.	Mk.	Freq.	Reading	Correct	Measure-	Limit	Margin	Detector	Comment
			Level	Factor	ment				
1		32.9100	41.14	-19.49	21.65	30.00	-8.35	QP	
2	*	137.6700	43.18	-17.29	25.89	30.00	-4.11	QP	
3	!	177.4400	42.61	-16.97	25.64	30.00	-4.36	QP	
4		427.7000	37.79	-11.81	25.98	37.00	-11.02	QP	
5		761.3800	32.58	-7.20	25.38	37.00	-11.62	QP	
6		971.8700	33.05	-5.29	27.76	37.00	-9.24	QP	

Test Voltage	AC 110V/60Hz	Polarization	Horizontal
Test Mode	Mode 1		



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1	51.3400	36.54	-17.78	18.76	30.00	-11.24	QP		
2	138.6400	38.42	-17.98	20.44	30.00	-9.56	QP		
3	427.7000	43.19	-12.43	30.76	37.00	-6.24	QP		
4	517.9100	37.83	-10.86	26.97	37.00	-10.03	QP		
5 *	769.1400	39.25	-7.59	31.66	37.00	-5.34	QP		
6	944.7100	36.02	-5.64	30.38	37.00	-6.62	QP		

3.2 RADIATED EMISSIONS ABOVE 1 GHZ

3.2.1 LIMITS

Class B equipment above 1 GHz

Frequency Range MHz	Measurement			Class B limits dB(µV/m)
	Facility	Distance m	Detector type/bandwidth	
1000 - 3000	FSOATS	3	Average / 1 MHz	50
3000 - 6000			Peak / 1 MHz	54
1000 - 3000			Average / 1 MHz	70
3000 - 6000			Peak / 1 MHz	74

Notes:

- (1) The limit for radiated test was performed according to as following: EN 55032
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dB_BV/m)=20log Emission level (uV/m).
- (4) The test result calculated as following:
Measurement Value = Reading Level + Correct Factor
Correct Factor = Antenna Factor + Cable Loss - Amplifier Gain(if use)
Margin Level = Measurement Value - Limit Value

Required highest frequency for radiated measurement

Highest internal frequency (F _x)	Highest measured frequency
F _x ≤ 108 MHz	1 GHz
108 < F _x ≤ 500 MHz	2 GHz
500 < F _x ≤ 1000 MHz	5 GHz
F _x > 1 GHz	5 × F _x up to a maximum of 6 GHz

3.2.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Horn Antenna	ETS	3115	9605-4803	Jul.07, 2025
2	MXE EMI Receiver	Agilent	N9038A	MY53220133	Jun. 01, 2025
3	Preamplifier	EMC INSTRUMENT	EMC118A45SE	981003	Oct. 29, 2025
4	Measurement Software	Farad	EZ-EMC Ver.BTL-2ANT-1	N/A	N/A
5	Multi-Device Controller	ETS-Lindgren	2090	N/A	N/A
6	Controller	MF	MF-7802	MF780208159	N/A
7	Cable	RegalWay	RWLP50-4.0A-S MSM-9M	N/A	Sep. 02, 2025
8	Cable	RW	RWLP50-4.0A-N MRASM-1M	N/A	Sep. 02, 2025
9	Cable	RW	RWLP50-4.0A-N MRASM-4M	N/A	Sep. 02, 2025

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.

All calibration period of equipment list is one year.

3.2.3 TEST PROCEDURE


- a. The measuring distance of 3 m shall be used for measurements. The EUT was placed on the top of a rotating table 0.8 meter above the ground at a 10 meter semi-anechoic chamber. The table was rotated 360 degrees to determine the position of the highest radiation.
- b. The height of the equipment or of the substitution antenna shall be 0.8 m, the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- c. The initial step in collecting radiated emission data is a receiver peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then AVG detector mode re-measured.
- d. All readings are Peak Mode value unless otherwise stated AVG in column of Note. If the Peak Mode Measured value compliance with the Peak Limits and lower than AVG Limits, the EUT shall be deemed to meet both Peak & AVG Limits and then only Peak Mode was measured, but AVG Mode didn't perform.
- e. For the actual test configuration, please refer to the related Item - EUT Test Photos.

3.2.4 DEVIATION FROM TEST STANDARD

The limit of the EN 55032:2015+A1:2020&AS/NZS CISPR 32:2015+AMD1:2020&CISPR 32:2015+AMD1:2019 standard deviates from the requirements, but the limit of the EN 55032:2015+A11:2020 standard is more stringent and can be covered, so the test data meets the EN 55032:2015+A1:2020 &AS/NZS CISPR 32:2015+AMD1:2020&CISPR 32:2015+AMD1:2019 standard.

3.2.5 TEST SETUP

ABOVE 1 GHZ



3.2.6 MEASUREMENT DISTANCE




Figure C.1 – Measurement distance





Figure C.2 – Boundary of EUT, Local AE and associated cabling


3.2.7 TEST RESULTS

Test Voltage	AC 230V/50Hz	Polarization	Vertical
Test Mode	Mode 1		




No.	Mk.	Freq.	Reading Level	Correct Factor	Measure- ment	Limit	Margin		
		MHz	dBuV	dB	dBuV/m	dBuV/m	dB	Detector	Comment
1		1195.000	42.17	-5.37	36.80	70.00	-33.20	peak	
2		1195.000	31.93	-5.37	26.56	50.00	-23.44	AVG	
3		1712.500	40.90	-3.71	37.19	70.00	-32.81	peak	
4		1712.500	34.27	-3.71	30.56	50.00	-19.44	AVG	
5		2050.000	42.62	-2.43	40.19	70.00	-29.81	peak	
6		2050.000	33.52	-2.43	31.09	50.00	-18.91	AVG	
7		2585.000	41.10	-1.04	40.06	70.00	-29.94	peak	
8		2585.000	31.16	-1.04	30.12	50.00	-19.88	AVG	
9		3097.500	41.86	0.65	42.51	74.00	-31.49	peak	
10		3097.500	31.80	0.65	32.45	54.00	-21.55	AVG	
11		4107.500	45.45	2.83	48.28	74.00	-25.72	peak	
12	*	4107.500	36.06	2.83	38.89	54.00	-15.11	AVG	

Test Voltage	AC 230V/50Hz	Polarization	Horizontal
Test Mode	Mode 1		




No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1		1592.500	44.02	-4.19	39.83	70.00	-30.17	peak	
2		1592.500	35.08	-4.19	30.89	50.00	-19.11	AVG	
3		2057.500	42.53	-2.41	40.12	70.00	-29.88	peak	
4		2057.500	32.59	-2.41	30.18	50.00	-19.82	AVG	
5		2692.500	41.64	-0.65	40.99	70.00	-29.01	peak	
6		2692.500	30.77	-0.65	30.12	50.00	-19.88	AVG	
7		3235.000	41.40	0.97	42.37	74.00	-31.63	peak	
8		3235.000	31.09	0.97	32.06	54.00	-21.94	AVG	
9		4107.500	44.52	2.83	47.35	74.00	-26.65	peak	
10	*	4107.500	37.95	2.83	40.78	54.00	-13.22	AVG	
11		5382.500	53.77	4.07	57.84	74.00	-16.16	peak	
12		5382.500	29.37	4.07	33.44	54.00	-20.56	AVG	

Test Voltage	AC 110V/60Hz	Polarization	Vertical
Test Mode	Mode 1		



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV/m	Limit dBuV/m	Margin dB	Detector	Comment
1		1597.500	43.66	-4.17	39.49	70.00	-30.51	peak	
2		1597.500	35.15	-4.17	30.98	50.00	-19.02	AVG	
3		2062.500	42.29	-2.39	39.90	70.00	-30.10	peak	
4		2062.500	32.84	-2.39	30.45	50.00	-19.55	AVG	
5		3095.000	41.60	0.65	42.25	74.00	-31.75	peak	
6		3095.000	31.41	0.65	32.06	54.00	-21.94	AVG	
7		4107.500	44.80	2.83	47.63	74.00	-26.37	peak	
8	*	4107.500	38.15	2.83	40.98	54.00	-13.02	AVG	
9		5397.500	46.42	4.09	50.51	74.00	-23.49	peak	
10		5397.500	36.69	4.09	40.78	54.00	-13.22	AVG	
11		5720.000	38.64	4.43	43.07	74.00	-30.93	peak	
12		5720.000	28.63	4.43	33.06	54.00	-20.94	AVG	

Test Voltage	AC 110V/60Hz	Polarization	Horizontal
Test Mode	Mode 1		



No.	Mk.	Freq.	Reading	Correct	Measure-	Limit	Margin	Comment
			Level	Factor	ment			
		MHz	dBuV	dB	dBuV/m	dB	Detector	Comment
1		1632.500	42.98	-4.02	38.96	70.00	-31.04	peak
2		1632.500	35.47	-4.02	31.45	50.00	-18.55	AVG
3		2075.000	42.09	-2.37	39.72	70.00	-30.28	peak
4		2075.000	34.46	-2.37	32.09	50.00	-17.91	AVG
5		2692.500	41.81	-0.65	41.16	70.00	-28.84	peak
6		2692.500	30.90	-0.65	30.25	50.00	-19.75	AVG
7		3235.000	40.82	0.97	41.79	74.00	-32.21	peak
8		3235.000	30.12	0.97	31.09	54.00	-22.91	AVG
9		4180.000	45.02	2.80	47.82	74.00	-26.18	peak
10		4180.000	37.98	2.80	40.78	54.00	-13.22	AVG
11		5380.000	52.86	4.07	56.93	74.00	-17.07	peak
12	*	5380.000	41.96	4.07	46.03	54.00	-7.97	AVG

3.3 CONDUCTED EMISSION MEASUREMENT AT AC MAINS POWER PORTS

3.3.1 LIMITS

Requirements for conducted emissions from AC mains power ports of Class B equipment

Frequency Range MHz	Coupling Device	Detector Type / bandwidth	Class B Limits (dB(μV))
0.15 - 0.5	AMN	Quasi Peak / 9 kHz	66-56
0.5 - 5			56
5 - 30			60
0.15 - 0.5	AMN	Average / 9 kHz	56-46
0.5 - 5			46
5 - 30			50

NOTE:

(1) The test result calculated as following:

Measurement Value = Reading Level + Correct Factor

Correct Factor = Insertion Loss + Cable Loss + Attenuator Factor(if use)

Margin Level = Measurement Value – Limit Value

3.3.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	TWO-LINE V-NETWORK	R&S	ENV216	100526	May 31, 2025
2	EMI Test Receiver	R&S	ESCI	100895	Jan. 10, 2026
3	Cable	N/A	RWLP50-4.0A-KJ-S MSM-6M	6M	Apr. 02, 2026
4	Measurement Software	Farad	EZ-EMC Ver.NB-03A1-01	N/A	N/A
5	Artificial-Mains Network	Schwarzbeck	NSLK 8127	8127685	Dec. 06, 2025

Remark: "N/A" denotes no model name, no serial no. or no calibration specified.

All calibration period of equipment list is one year.


3.3.3 TEST PROCEDURE

- a. The EUT was placed 0.8 meters from the horizontal ground plane with EUT being connected to the power mains through a line impedance stabilization network (LISN). All other support equipment powered from additional LISN(s). The LISN provide 50 Ohm/ 50uH of coupling impedance for the measuring instrument.
- b. Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle 30 to 40 cm long.
- c. I/O cables that are not connected to a peripheral shall be bundled in the center. The end of the cable may be terminated, if required, using the correct terminating impedance. The overall length shall not exceed 1 m.
- d. LISN at least 80 cm from nearest part of EUT chassis.
- e. For the actual test configuration, please refer to the related Item –EUT Test Photos.

3.3.4 DEVIATION FROM TEST STANDARD


No deviation

3.3.5 TEST SETUP




3.3.6 TEST RESULTS

Test Voltage	AC 230V/50Hz	Phase	Line
Test Mode	Mode 1		




No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Margin dB	Detector	Comment
1		0.1700	37.94	9.63	47.57	64.96	-17.39	QP	
2	*	0.1700	28.90	9.63	38.53	54.96	-16.43	AVG	
3		0.2100	34.96	9.64	44.60	63.21	-18.61	QP	
4		0.2100	25.40	9.64	35.04	53.21	-18.17	AVG	
5		0.2420	29.04	9.65	38.69	62.03	-23.34	QP	
6		0.2420	20.30	9.65	29.95	52.03	-22.08	AVG	
7		0.5580	24.65	9.69	34.34	56.00	-21.66	QP	
8		0.5580	15.90	9.69	25.59	46.00	-20.41	AVG	
9		1.7900	20.71	9.73	30.44	56.00	-25.56	QP	
10		1.7900	11.20	9.73	20.93	46.00	-25.07	AVG	
11		2.4500	19.61	9.75	29.36	56.00	-26.64	QP	
12		2.4500	12.30	9.75	22.05	46.00	-23.95	AVG	

Test Voltage	AC 230V/50Hz	Phase	Neutral
Test Mode	Mode 1		




No.	Mk.	Freq.	Reading	Correct	Measure-	Limit	Margin	
			Level	Factor	ment		dB	dBuV
1		0.1700	38.44	9.62	48.06	64.96	-16.90	QP
2	*	0.1700	30.50	9.62	40.12	54.96	-14.84	AVG
3		0.2020	36.45	9.63	46.08	63.53	-17.45	QP
4		0.2020	27.80	9.63	37.43	53.53	-16.10	AVG
5		0.2420	30.91	9.64	40.55	62.03	-21.48	QP
6		0.2420	21.60	9.64	31.24	52.03	-20.79	AVG
7		0.4940	26.37	9.67	36.04	56.10	-20.06	QP
8		0.4940	17.50	9.67	27.17	46.10	-18.93	AVG
9		0.5620	26.54	9.68	36.22	56.00	-19.78	QP
10		0.5620	17.90	9.68	27.58	46.00	-18.42	AVG
11		1.5180	23.70	9.72	33.42	56.00	-22.58	QP
12		1.5180	14.30	9.72	24.02	46.00	-21.98	AVG

Test Voltage	AC 110V/60Hz	Phase	Line
Test Mode	Mode 1		



No.	Mk.	Freq.	Reading	Correct	Measure-	Limit	Margin	Detector	Comment
			Level	Factor	ment				
1		0.1500	38.33	9.62	47.95	66.00	-18.05	QP	
2	*	0.1500	29.60	9.62	39.22	56.00	-16.78	AVG	
3		0.1620	35.78	9.63	45.41	65.36	-19.95	QP	
4		0.1620	26.40	9.63	36.03	55.36	-19.33	AVG	
5		0.2460	32.04	9.65	41.69	61.89	-20.20	QP	
6		0.2460	23.50	9.65	33.15	51.89	-18.74	AVG	
7		0.4340	24.51	9.68	34.19	57.18	-22.99	QP	
8		0.4340	15.40	9.68	25.08	47.18	-22.10	AVG	
9		0.5260	24.24	9.68	33.92	56.00	-22.08	QP	
10		0.5260	15.60	9.68	25.28	46.00	-20.72	AVG	
11		2.0500	19.75	9.73	29.48	56.00	-26.52	QP	
12		2.0500	10.50	9.73	20.23	46.00	-25.77	AVG	

Test Voltage	AC 110V/60Hz	Phase	Neutral
Test Mode	Mode 1		



No.	Mk.	Freq. MHz	Reading Level dBuV	Correct Factor dB	Measure- ment dBuV	Limit dBuV	Margin dB	Detector	Comment
1		0.1500	38.88	9.60	48.48	66.00	-17.52	QP	
2		0.1500	29.60	9.60	39.20	56.00	-16.80	AVG	
3		0.1980	30.72	9.63	40.35	63.69	-23.34	QP	
4		0.1980	21.30	9.63	30.93	53.69	-22.76	AVG	
5		0.2500	30.32	9.63	39.95	61.76	-21.81	QP	
6		0.2500	21.50	9.63	31.13	51.76	-20.63	AVG	
7		0.2700	28.67	9.64	38.31	61.12	-22.81	QP	
8		0.2700	19.50	9.64	29.14	51.12	-21.98	AVG	
9		0.4940	28.26	9.67	37.93	56.10	-18.17	QP	
10	*	0.4940	19.80	9.67	29.47	46.10	-16.63	AVG	
11		1.4300	23.84	9.71	33.55	56.00	-22.45	QP	
12		1.4300	14.50	9.71	24.21	46.00	-21.79	AVG	

3.4 HARMONIC CURRENT EMISSIONS TEST

3.4.1 LIMITS

The power consumption is less than 75W, there is no limit applied.

3.4.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Harmonics and Flicker Analyzer	California Instruments	PACS-1	72344	Jun. 01, 2025
2	3KVA AC Power source	California Instruments	3001ix	56309	Jun. 01, 2025
3	Measurement Software	California	CTS4.0 Version 4.29	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.


3.4.3 TEST PROCEDURE

- a. The EUT was placed on the top of a wooden table 0.8 meters above the ground and operated to produce the maximum harmonic components under normal operating conditions.
- b. The classification of EUT is according to of EN 61000-3-2. The EUT is classified as Class D.
- c. The correspondent test program of test instrument to measure the current harmonics emanated from EUT is chosen. The measure time shall be not less than the time necessary for the EUT to be exercised.

3.4.4 DEVIATION FROM TEST STANDARD

No deviation


3.4.5 TEST SETUP




3.4.6 TEST RESULTS

Harmonics – Class-D	
Test Voltage	AC 230V/50Hz
Test Mode	Mode 1

Current & voltage waveforms



Harmonics and Class D limit line European Limits



Test result: N/L Worst harmonics H0-0.0% of 150% limit, H0-0% of 100% limit

Current Test Result Summary (Run time)	
Test Voltage	AC 230V/50Hz
Test Mode	Mode 1

Highest parameter values during test:

V_RMS (Volts): 229.94 Frequency(Hz): 50.00
I_Peak (Amps): 1.010 I_RMS (Amps): 0.228
I_Fund (Amps): 0.104 Crest Factor: 4.448
Power (Watts): 21.6 Power Factor: 0.415

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.001	0.000	N/A	0.002	0.000	N/A	N/L
3	0.091	0.073	N/A	0.093	0.110	N/A	N/L
4	0.001	0.000	N/A	0.002	0.000	N/A	N/L
5	0.087	0.041	N/A	0.088	0.062	N/A	N/L
6	0.001	0.000	N/A	0.001	0.000	N/A	N/L
7	0.081	0.022	N/A	0.082	0.032	N/A	N/L
8	0.001	0.000	N/A	0.001	0.000	N/A	N/L
9	0.073	0.011	N/A	0.074	0.016	N/A	N/L
10	0.001	0.000	N/A	0.001	0.000	N/A	N/L
11	0.065	0.008	N/A	0.065	0.011	N/A	N/L
12	0.001	0.000	N/A	0.001	0.000	N/A	N/L
13	0.055	0.006	N/A	0.056	0.010	N/A	N/L
14	0.000	0.000	N/A	0.001	0.000	N/A	N/L
15	0.046	0.006	N/A	0.047	0.008	N/A	N/L
16	0.000	0.000	N/A	0.001	0.000	N/A	N/L
17	0.037	0.005	N/A	0.037	0.007	N/A	N/L
18	0.000	0.000	N/A	0.001	0.000	N/A	N/L
19	0.028	0.004	N/A	0.028	0.007	N/A	N/L
20	0.000	0.000	N/A	0.001	0.000	N/A	N/L
21	0.020	0.004	N/A	0.021	0.006	N/A	N/L
22	0.000	0.000	N/A	0.001	0.000	N/A	N/L
23	0.014	0.004	N/A	0.015	0.005	N/A	N/L
24	0.000	0.000	N/A	0.001	0.000	N/A	N/L
25	0.010	0.003	N/A	0.010	0.005	N/A	N/L
26	0.000	0.000	N/A	0.001	0.000	N/A	N/L
27	0.008	0.003	N/A	0.008	0.005	N/A	N/L
28	0.000	0.000	N/A	0.001	0.000	N/A	N/L
29	0.008	0.003	N/A	0.008	0.004	N/A	N/L
30	0.000	0.000	N/A	0.000	0.000	N/A	N/L
31	0.008	0.003	N/A	0.008	0.004	N/A	N/L
32	0.000	0.000	N/A	0.000	0.000	N/A	N/L
33	0.008	0.003	N/A	0.008	0.004	N/A	N/L
34	0.000	0.000	N/A	0.000	0.000	N/A	N/L
35	0.008	0.002	N/A	0.008	0.004	N/A	N/L
36	0.000	0.000	N/A	0.000	0.000	N/A	N/L
37	0.006	0.002	N/A	0.007	0.003	N/A	N/L
38	0.000	0.000	N/A	0.000	0.000	N/A	N/L
39	0.005	0.002	N/A	0.005	0.003	N/A	N/L
40	0.000	0.000	N/A	0.000	0.000	N/A	N/L

Note: The EUT power level is below 75.0 Watts and therefore has no defined limits

Voltage Source Verification Data (Run time)	
Test Voltage	AC 230V/50Hz
Test Mode	Mode 1

Highest parameter values during test:

Voltage (Vrms): 229.94 Frequency(Hz): 50.00
I Peak (Amps): 1.010 I RMS (Amps): 0.228
I Fund (Amps): 0.104 Crest Factor: 4.448
Power (Watts): 21.6 Power Factor: 0.415

Harm#	Harmonics	V-rms	Limit V-rms	% of Limit	Status
2		0.156	0.460	33.82	OK
3		0.513	0.2069	24.80	OK
4		0.071	0.460	15.35	OK
5		0.039	0.920	4.20	OK
6		0.035	0.460	7.69	OK
7		0.063	0.690	9.13	OK
8		0.020	0.460	4.45	OK
9		0.038	0.460	8.32	OK
10		0.029	0.460	6.24	OK
11		0.051	0.230	22.02	OK
12		0.020	0.230	8.61	OK
13		0.033	0.230	14.20	OK
14		0.015	0.230	6.60	OK
15		0.041	0.230	17.86	OK
16		0.017	0.230	7.56	OK
17		0.027	0.230	11.64	OK
18		0.016	0.230	6.94	OK
19		0.032	0.230	13.94	OK
20		0.020	0.230	8.56	OK
21		0.017	0.230	7.31	OK
22		0.011	0.230	4.98	OK
23		0.021	0.230	9.15	OK
24		0.006	0.230	2.76	OK
25		0.014	0.230	6.22	OK
26		0.009	0.230	3.91	OK
27		0.013	0.230	5.61	OK
28		0.009	0.230	3.72	OK
29		0.015	0.230	6.74	OK
30		0.006	0.230	2.47	OK
31		0.010	0.230	4.54	OK
32		0.006	0.230	2.43	OK
33		0.017	0.230	7.57	OK
34		0.004	0.230	1.85	OK
35		0.012	0.230	5.11	OK
36		0.003	0.230	1.31	OK
37		0.012	0.230	5.32	OK
38		0.004	0.230	1.61	OK
39		0.009	0.230	4.02	OK
40		0.006	0.230	2.75	OK

3.5 VOLTAGE FLUCTUATIONS (FLICKER) TEST

3.5.1 LIMITS

Tests	Limits	Descriptions
	EN 61000-3-3	
Pst	≤ 1.0, Tp= 10 min.	Short Term Flicker Indicator
Plt	≤ 0.65, Tp= 2 hr.	Long Term Flicker Indicator
dc	≤ 3.3%	Relative Steady-State V-Change
dmax	≤ 4%	Maximum Relative V-change
d (t)	≤ 500 ms	Relative V-change characteristic

3.5.2 MEASUREMENT INSTRUMENTS LIST

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Harmonics and Flicker Analyzer	California Instruments	PACS-1	72344	Jun. 01, 2025
2	3KVA AC Power source	California Instruments	3001ix	56309	Jun. 01, 2025
3	Measurement Software	California	CTS4.0 Version 4.29	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.


3.5.3 TEST PROCEDURE

- a. Tests was performed according to the Test Conditions/Assessment of Voltage Fluctuations specified in EN 61000-3-3 depend on which standard adopted for compliance measurement.
- b. All types of harmonic current and/or voltage fluctuation in this report are assessed by direct measurement using flicker-meter.

3.5.4 DEVIATION FROM TEST STANDARD

No deviation


3.5.5 TEST SETUP



3.5.6 TEST RESULTS


Test Voltage	AC 230V/50Hz
Test Mode	Mode 1

Pst and limit line



European Limits

Plt and limit line



Parameter values recorded during the test:

Vrms at the end of test (Volt): 229.83

T-max (mS): 0

Highest dc (%): 0.00

Highest dmax (%): 0.00

Highest Pst (10 min. period): 0.273

Highest Plt (2 hr. period): 0.119

Test limit (mS): 500.0

Test limit (%): 3.30

Test limit (%): 4.00

Test limit: 1.000

Test limit: 0.650

Pass

Pass

Pass

Pass

Pass

4. EMC IMMUNITY TEST

4.1 STANDARD COMPLIANCE/SEVERITY LEVEL/CRITERIA

Tests Standard No.	Test Specification Level / Test Mode	Test Ports	Criteria
Electrostatic discharge IEC 61000-4-2 (ESD)	±8kV air discharge ±4kV contact discharge (Direct Mode)	Enclosure	B
	±4kV HCP discharge ±4kV VCP discharge (Indirect Mode)	Enclosure	B
Continuous RF electromagnetic field disturbances,swept test IEC 61000-4-3 (RS)	80 MHz to 1000 MHz 3V/m(unmodulated, r.m.s), 1 kHz, 80%, AM modulated	Enclosure	A
Continuous RF electromagnetic field disturbances,spot test IEC 61000-4-3 (RS)	1800 MHz, 2600MHz, 3500 MHz, 5000MHz(±1 %) 3V/m(unmodulated, r.m.s), 1 kHz, 80%, AM modulated	Enclosure	A
Electrical fast transient/burst immunity IEC 61000-4-4 (EFT)	±0.5kV(peak) 5/50ns Tr/Th 5kHz Repetition Frequency (100kHz Repetition Frequency for xDSL port)	Analogue/digital data ports (NOTE 2)	B
	±0.5kV(peak) 5/50ns Tr/Th 5kHz Repetition Frequency	DC network power ports (NOTE 2)	B
	±1 kV(peak) 5/50ns Tr/Th 5kHz Repetition Frequency	AC mains power ports	B

Surge immunity IEC 61000-4-5 (Surge)	Port Type: unshielded symmetrical Apply: lines to ground		
	Primary protection is Intended ±1 kV and ±4 kV 10/700(5/320)Tr/Th μ s	Analogue/digital data ports (NOTE 1) & (NOTE 2)	C
	Primary protection is not Intended ±1 kV 10/700(5/320) Tr/Th μ s		C
	Port type: coaxial or shielded Apply: shield to ground		
	±0.5 kV 1.2/50(8/20) Tr/Th μ s	Analogue/digital data ports (NOTE 1) & (NOTE 2)	B
	line to reference ground for each individual line: ±0.5 kV(peak) 1.2/50(8/20) Tr/Th μ s	DC network power ports (NOTE 2)	B
	±1 kV(peak) 1.2/50(8/20) Tr/Th μ s (line to line) ±2 kV(peak) 1.2/50(8/20) Tr/Th μ s (line to earth or ground)	AC mains power ports	B
	0.15 MHz to 10 MHz 3V(unmodulated, r.m.s), 10 MHz to 30 MHz 3V to 1V(unmodulated, r.m.s), 30 MHz to 80 MHz 1V(unmodulated, r.m.s), 1kHz 80%, AM 150 Ω source impedance	Analogue/digital data ports (NOTE 2)	A
	0.15 MHz to 10 MHz 3V(unmodulated, r.m.s), 10 MHz to 30 MHz 3V to 1V(unmodulated, r.m.s), 30 MHz to 80 MHz 1V(unmodulated, r.m.s), 1kHz 80%, AM 150 Ω source impedance	DC network power ports (NOTE 2)	A
	0.15 MHz to 10 MHz 3V(unmodulated, r.m.s), 10 MHz to 30 MHz 3V to 1V(unmodulated, r.m.s), 30 MHz to 80 MHz 1V(unmodulated, r.m.s), 1kHz 80%, AM 150 Ω source impedance	AC mains power ports	A

Power frequency magnetic field immunity IEC 61000-4-8 (PFMF)	50 Hz or 60Hz, 1A/m(r.m.s)	Enclosure	A
Voltage dips, short interruptions and voltage variations immunity IEC 61000-4-11 (Dips)	Voltage dips: Residual voltage<5% 0.5 cycle Residual voltage<70% 25 cycle(50Hz), 30 cycle (60Hz) Voltage interruptions: Residual voltage<5% 250 cycle (50Hz), 300 cycle (60Hz)	AC Power Ports	B C C
Broadband impulse noise disturbances,repetitive (BIN-R)	0.15 MHz to 0.5 MHz 107 dBuV 0.5 MHz to 10 MHz 107 dBuV to 36 dBuV 10 MHz to 30 MHz 36 dBuV to 30 dBuV 0.70 ms 8.3 ms(for 60Hz) 10 ms(for 50Hz)	Analogue/digital data ports (Applicable only to CPE xDSL ports)	A
Broadband impulse noise disturbances,isolated (BIN-I)	0.15 MHz to 30 MHz 110 dBuV 0.24 ms 10 ms 300 ms	Analogue/digital data ports (Apply period based on the AC mains frequency)	A
	0.15 MHz to 30 MHz 110 dBuV	Analogue/digital data ports (Applicable only to CPE xDSL ports)	B
	0.24 ms 10 ms 300 ms	Analogue/digital data ports (Apply all burst durations)	B

Note.

- 1) Applicable only to ports which, according to the manufacturer's specification, may connect directly to outdoor cables.
- 2) Applicable only to ports which, according to the manufacturer's specification, support cable lengths greater than 3 m.

4.2 GENERAL PERFORMANCE CRITERIA

According to **EN 55035** standards, the general performance criteria as following:

Criterion A	The equipment shall continue to operate as intended without operator intervention. No degradation of performance, loss of function or change of operating state is allowed below a performance level specified by the manufacturer when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance. If the minimum performance level or the permissible performance loss is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.
Criterion B	During the application of the disturbance, degradation of performance is allowed. However, no unintended change of actual operating state or stored data is allowed to persist after the test. After the test, the equipment shall continue to operate as intended without operator intervention; no degradation of performance or loss of function is allowed, below a performance level specified by the manufacturer, when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance. If the minimum performance level (or the permissible performance loss), or recovery time, is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.
Criterion C	Loss of function is allowed, provided the function is self-recoverable, or can be restored by the operation of the controls by the user in accordance with the manufacturer's instructions. A reboot or re-start operation is allowed. Information stored in non-volatile memory, or protected by a battery backup, shall not be lost.

4.3 ANNEX D (NORMATIVE) - DISPLAY AND DISPLAY OUTPUT FUNCTION

4.3.1 PERFORMANCE CRITERIA

Performance criterion A

for continuous radiated and conducted disturbances tests:

Apply criterion A as defined in GENERAL PERFORMANCE CRITERIA. Additionally, an increase in any degradation greater than

just perceptible by observation of the image shall not occur as a consequence of the application of the test. Examples of such degradations are:

- superimposed patterning;
- positional disturbances due to synchronisation errors;
- geometric distortion;
- change of contrast or brightness;
- picture artefacts;
- freezing or disturbance of motion;
- image loss;
- video data or decoding errors.

Performance criterion A

for the power frequency magnetic field tests:

Alternative 1: A continuous magnetic field of 1 A/m:

The jitter (in mm) shall not exceed the value
$$\frac{(\text{character height in mm} + 0,3) \times 2,5}{33,3}$$

Performance criterion B:

Apply criterion B as defined in GENERAL PERFORMANCE CRITERIA.

Performance criterion C:

Apply criterion C as defined in GENERAL PERFORMANCE CRITERIA.

4.4 ANNEX G (NORMATIVE) - AUDIO OUTPUT FUNCTION

4.4.1 PERFORMANCE CRITERIA

Performance criterion A:

For devices that support telephony functions the limits of Table G.3 shall apply.

With respect to Table G.3:

- the interference ratio (electrical or acoustic) shall meet the limits in column 3; or,
- the acoustic level of the demodulated audio shall be less than the limits in column 4; or,
- the digitally coded level of demodulated audio shall be less than limits in column 5; or,
- the analogue level of the demodulated audio shall be less than the limits in column 6.

Table G.3 – Performance criterion A – Limits for devices supporting telephony

Type of immunity test	Frequency range MHz	Acoustic or electrical interference ratio	Equivalent direct measurement		
			dB (SPL)	Digital dBm0	Analogue dBm
Conducted	0,15 to 30	-20 dB	55	-50	-50
	30 to 80	-10 dB	65	-40	-40
Radiated	80 to 1000	0 dB	75	-30	-30

For terminals connected to digital wired network ports (such as Ethernet, ISDN), measurements of the demodulated 1 kHz may be performed on a remote AE, ideally of the same design.

For all other devices:

The measured acoustic interference ratio and/or the measured electrical interference ratio during the test shall be -20 dB or better.

Performance criterion B:

Use the general performance criterion B. See GENERAL PERFORMANCE CRITERIA.

Performance criterion C:

Use the general performance criterion C. See GENERAL PERFORMANCE CRITERIA.

4.5 ELECTROSTATIC DISCHARGE IMMUNITY TEST (ESD)

4.5.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-2
Discharge Impedance	330 ohm / 150 pF
Required Performance	B
Discharge Voltage	Air Discharge: $\pm 2\text{kV}$, $\pm 4\text{kV}$, $\pm 8\text{kV}$ Contact Discharge: $\pm 2\text{kV}$, $\pm 4\text{kV}$
Polarity	Positive & Negative
Number of Discharge	20 times at each test point
Discharge Mode	Single Discharge
Discharge Period	1 second

4.5.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	ESD Generator	TESEQ AG	NSG 437	450	Nov. 13, 2025

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.5.3 TEST PROCEDURE

The test generator necessary to perform direct and indirect application of discharges to the EUT in the following manner:

- The test shall be performed with single discharges. On each pre-selected point at least 10 single discharges (in the most sensitive polarity) shall be applied.

NOTE 1 The minimum number of discharges applied is depending on the EUT; for products with synchronized circuits the number of discharges should be larger.

For the time interval between successive single discharges an initial value of 1 s is recommended. Longer intervals may be necessary to determine whether a system failure has occurred.

NOTE 2 The points to which the discharges should be applied may be selected by means of an exploration carried out at a repetition rate of 20 discharges per second, or more.

Vertical Coupling Plane (VCP):

The coupling plane, of dimensions 0.5m x 0.5m, is placed parallel to, and positioned at a distance 0.1m from, the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge.

Horizontal Coupling Plane (HCP):

The coupling plane is placed under to the EUT. The generator shall be positioned vertically at a distance of 0.1m from the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge.


- For TABLE-TOP equipment:

The configuration consisted of a wooden table 0.8 meters high standing on the Ground Reference Plane. The GRP consisted of a sheet of aluminum at least 0.25mm thick, and 2.5 meters square connected to the protective grounding system. A Horizontal Coupling Plane (1.6m x 0.8m) was placed on the table and attached to the GRP by means of a cable with 940k total impedance. The equipment under test was installed in a representative system as described in IEC 61000-4-2, and its cables were placed on the HCP and isolated by an insulating support of 0.5mm thickness. A distance of 1-meter minimum was provided between the EUT and the walls of the laboratory and any other metallic structure.

4.5.4 DEVIATION FROM TEST STANDARD

No deviation

4.5.5 TEST SETUP



4.5.6 TEST RESULTS

Test Voltage	AC 230V/50Hz											
Test Mode	Mode 1-10											



Mode	Air Discharge								Contact Discharge					
	2kV		4kV		8kV		- kV		2kV		4kV		- kV	
Location	P	N	P	N	P	N	P	N	P	N	P	N	P	N
1	A	A	A	A	A	A	-	-	A	A	B	B	-	-
2	A	A	A	A	A	A	-	-	-	-	-	-	-	-
3	A	A	A	A	A	A	-	-	-	-	-	-	-	-
4	A	A	A	A	B	B	-	-	-	-	-	-	-	-
5	A	A	A	A	A	A	-	-	-	-	-	-	-	-
Criteria	B						-		B				-	
Result	B						-		B				-	


Mode	HCP Contact Discharge						VCP Contact Discharge					
	2kV		4kV		- kV		2kV		4kV		- kV	
Location	P	N	P	N	P	N	P	N	P	N	P	N
Left side	A	A	A	A	-	-	A	A	A	A	-	-
Right side	A	A	A	A	-	-	A	A	A	A	-	-
Front side	A	A	A	A	-	-	A	A	A	A	-	-
Rear side	A	A	A	A	-	-	A	A	A	A	-	-
Criteria	B				-		B				-	
Result	A				-		A				-	

Note:

- 1) P/N denotes the Positive/Negative polarity of the output voltage.
- 2) N/A - denotes test is not applicable in this test report

PHOTO(S) SHOWN THE LOCATION(S) OF ESD EVALUATED





4.6 RADIATED, RADIO-FREQUENCY, ELECTROMAGNETIC FIELD IMMUNITY TEST (RS)

4.6.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-3
Required Performance	A
Frequency Range	80 MHz - 1000 MHz, 1800 MHz, 2600 MHz, 3500 MHz, 5000MHz ($\pm 1\%$)
Field Strength	3 V/m(unmodulated, r.m.s)
Modulation	1 kHz Sine Wave, 80%, AM Modulation
Frequency Step	1% of the preceding frequency.
Polarity of Antenna	Horizontal and Vertical
Test Distance	3 m
Antenna Height	1.55 m
Dwell Time	3 seconds

4.6.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Antenna	ETS	3142B	00026419	N/A
2	Amplifier	AR	50S1G4A	326720	Dec. 06, 2025
3	MXG Analog Signal Generator	Agilent	N5181A	MY49060710	May 31, 2025
4	Power amplifier	MILMEGA	AS1860-50	1064834	Dec. 06, 2025
5	Microwave Log.-Per. Antenna	Schwarzbeck	STLP 9149	9149-277	N/A
6	Power amplifier	MILMEGA	80RF1000-250	1064833	Dec. 06, 2025
7	Measurement Software	Farad	(EZ-RS)V2.0.1.3	N/A	N/A
8	UPV Audio Analyzer	R&S	UPV	104259	Dec. 06, 2025

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.6.3 TEST PROCEDURE

The EUT and support equipment are in a fully-anechoic chamber.

The testing distance from antenna to the EUT was 3 meters.

For TABLE-TOP equipment:

The EUT installed in a representative system as described in IEC 61000-4-3 was placed on a non-conductive table 0.8 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

- a. The field strength level was 3 V/m(unmodulated, r.m.s).
- b. The frequency range is swept from 80 MHz to 1000 MHz, with the signal 80%amplitude modulated with a 1 kHz sine wave. Where the frequency range is swept incrementally, the step size was 1% of the preceding frequency.
- c. The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.
- d. The test was performed with the EUT exposed to both vertically and horizontally polarized fields on each of the four sides.

For Display and display output functions:

- a. The display quality evaluated by direct observation.
- b. For display output function evaluation, a suitable display device shall be connected. This device shall meet the immunity requirements for displays specified in this document. The screen size shall be typical for the display output. the diagonal screen size shall be at least 0,50 m.
- c. The display shall be observed under normal viewing conditions including viewing distance using a reduced ambient light level preferably in the range 15 lx to 20 lx. The viewing distance or settings of the video camera monitoring system shall be sufficient to provide visibility of the whole display. In the case of direct observation the selected viewing distance shall be recorded in the test report.

For Acoustic measurements:


- a. Apply an appropriate input signal to the EUT so that a sine wave (tone) at the frequency that will be used to modulate the applied disturbance (typically 1 kHz) is generated from the port under test at a level equal to the acoustic reference level.
- b. Record the resulting dB (SPL) level (or other appropriate dB unit) as the value of L_0 .
(BTL lab uses the software to take L_0 as the reference value and make it return to zero.)
- c. Change the input to the EUT so that the port under test is silent, or represents silence. This change shall not alter the terminating impedance at the EUT's input.
- d. Apply the RF disturbance to the applicable port of the EUT and record the resulting demodulated audio level in dB (SPL) (or other dB unit used in step d)) as the value of L_1 .
- e. Ensure that non-linear processing does not impact the measurements.
- f. Calculate the acoustic interference ratio using the following formula:
Acoustic interference ratio = $L_1 - L_0$.
(For step e-f, BTL lab proceeds the test with software and calculate Acoustic interference ratio = $L_1 - L_0$).

4.6.4 DEVIATION FROM TEST STANDARD

No deviation


4.6.5 TEST SETUP

- a) For Continuous induced RF disturbances



For Audio output function

(1) Audio output port



The filter is the audio filter specified in G.6.1 and is typically incorporated into the audio meter. Additional filtering might be necessary to ensure that the RF disturbance signal does not interfere with the measurement.

4.6.6 TEST RESULTS


Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-10

Frequency Range (MHz)	RF Field Position	R.F. Field Strength	Modulation	Azimuth	Criterion	Result
80 - 1000	H / V	3V/m	AM Modulated 1000Hz, 80%	0	A	A
				90		
				180		
				270		
1800, 2600, 3500, 5000 (±1%)	H / V	3V/m	AM Modulated 1000Hz, 80%	0	A	A
				90		
				180		
				270		


For Audio output function

(1) For Audio output port:

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1_Vertical_Front



Test Voltage	AC 230V/50Hz
Test Mode	Mode 1_Horizontal_Front



4.7 ELECTRICAL FAST TRANSIENT/BURST IMMUNITY TEST (EFT)

4.7.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-4
Required Performance	B
Test Voltage	AC mains power ports: ± 1 kV
Polarity	Positive & Negative
Impulse Frequency	5 kHz
Impulse Wave shape	5/50 ns
Burst Duration	15 ms
Burst Period	300 ms
Test Duration	1 min.

4.7.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Fast Transient Burst Simulator	Prima	EFT61004TA	PR190741004	May 31, 2025
2	Measurement Software	Prima	EFT_Series V1 .0.0.0.20180710	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.7.3 TEST PROCEDURE

For TABLE-TOP equipment:


The configuration consisted of a wooden table (0.8m high) standing on the Ground Reference Plane and should be located 0.1 m +/- 0.01m above the Ground Reference Plane. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system. A minimum distance of 0.5m was provided between the EUT and the walls of the laboratory or any other metallic structure.

- a. Both positive and negative polarity discharges were applied.
- b. The duration time of each test sequential was 1 minute.

4.7.4 DEVIATION FROM TEST STANDARD

No deviation

4.7.5 TEST SETUP



4.7.6 TEST RESULTS

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-10

EUT Ports Tested	Polarity	Repetition Frequency	Test Level	Criterion	Result
			1kV		
AC Power Port	Line (L)	+	5 kHz	B	B
		-	5 kHz	B	
	Neutral (N)	+	5 kHz	B	B
		-	5 kHz	B	
	Ground (PE)	+	5 kHz	B	B
		-	5 kHz	B	
	L+N	+	5 kHz	B	B
		-	5 kHz	B	
	L+PE	+	5 kHz	B	B
		-	5 kHz	B	
	N+PE	+	5 kHz	B	B
		-	5 kHz	B	
	L+N+PE	+	5 kHz	B	B
		-	5 kHz	B	

4.8 SURGE IMMUNITY TEST (SURGE)

4.8.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-5
Required Performance	B(AC mains power ports)
Wave-Shape	1.2/50(8/20) Tr/Th μ s combination wave
Test Voltage	AC mains power ports: ± 0.5 kV, ± 1 kV, ± 2 kV
Generator Source Impedance	2 Ω of the low-voltage power supply network. 12 Ω ($10\Omega+2\Omega$) of the low-voltage power supply network and ground.
Phase Angle, Polarity and Number of Tests	Five positive pulses line-to-neutral at 90°phase Five negative pulses line-to-neutral at 270°phase Five positive pulses line-to-earth at 90°phase Five negative pulses line-to-earth at 270°phase Five negative pulses neutral-to-earth at 90°phase Five positive pulses neutral-to-earth at 270°phase
Pulse Repetition Rate	1 time / min

4.8.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Lightning Surge Generator	Prima	SUG61005TB	PR190854067	May 31, 2025
2	Measurement Software	Prima	SUG_Series V1.0. 0.7.20190827	N/A	N/A

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.8.3 TEST PROCEDURE

a. For EUT power supply:

The surge is to be applied to the EUT power supply terminals via the capacitive coupling network. Decoupling networks are required in order to avoid possible adverse effects on equipment not under test that may be powered by the same lines, and to provide sufficient decoupling impedance to the surge wave. The power cord between the EUT and the coupling/decoupling networks shall be 2meters in length (or shorter).

b. For test applied to unshielded unsymmetrically operated interconnection lines of EUT :

The surge is applied to the lines via the capacitive coupling. The coupling /decoupling networks shall not influence the specified functional conditions of the EUT. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).


c. For test applied to unshielded symmetrically operated interconnection /telecommunication lines of EUT :

The surge is applied to the lines via gas arrestors coupling. Test levels below the ignition point of the coupling arrestor cannot be specified. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).

4.8.4 DEVIATION FROM TEST STANDARD

No deviation

4.8.5 TEST SETUP



4.8.6 TEST RESULTS

Test Voltage	AC 230V/50Hz				
Test Mode	Mode 1-10				

Wave Form EUT Ports Tested		1.2/50(8/20)Tr/Th μ s					Criterion	Result	
		Polarity	Phase	Voltage					
				1kV	-- kV	-- kV	-- kV		
AC	L - N	+	90°	B	-	-	-	B	B
		-	270°	B	-	-	-		

Wave Form EUT Ports Tested		1.2/50(8/20)Tr/Th μ s					Criterion	Result	
		Polarity	Phase	Voltage					
				2kV	-- kV	-- kV	-- kV		
AC	L - PE	+	90°	B	-	-	-	B	B
		-	270°	B	-	-	-		
	N - PE	-	90°	B	-	-	-	B	B
		+	270°	B	-	-	-		

4.9 IMMUNITY TO CONDUCTED DISTURBANCES, INDUCED BY RADIO-FREQUENCY FIELDS TEST (CS)

4.9.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-6
Required Performance	A
Frequency Range&Field Strength	0.15 MHz - 10 MHz: 3V (unmodulated, r.m.s.) 10 MHz - 30 MHz: 3V to 1V (unmodulated, r.m.s.) 30 MHz - 80 MHz: 1V (unmodulated, r.m.s.)
Modulation	1 kHz Sine Wave, 80%, AM Modulation
Frequency Step	1 % of the preceding frequency value
Dwell Time	3 seconds
The size of the EUT	See product appearance photos.

Remark:

The testing frequency range meets the requirements of the product standards listed in this report and is not affected by the size or expansion of the EUT.

4.9.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Measurement Software	Farad	EZ-CS (V2.0.1.4)	N/A	N/A
2	UPV Audio Analyzer	R&S	UPV	104259	Dec. 06, 2025
3	Coupling Decoupling Network	Teseq GmbH	CDN M016	35834	May 31, 2025
4	TEST SYSTEM FOR CONDUCTED AND RADIATED IMMUNITY	TESEQ	NSG 4070B	37513	Jun. 01, 2025
5	Attenuator	Teseq	100-SA-FFN-06	0163357	May 31, 2025
6	Power CDN	FCC	FCC-801-M2/M3-16A	100270	Dec. 06, 2025
7	UPV Audio Analyzer	R&S	UPV	104259	Dec. 06, 2025

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.9.3 TEST PROCEDURE

The EUT and support equipment, are placed on a table that is 0.8 meter above a metal ground plane measured 1m*1m min. and 0.65mm thick min.

The other condition as following manner:

- a. The field strength level was 3 V (unmodulated, r.m.s.)
- b. The frequency range is swept from 150 kHz to 80 MHz, with the signal 80%amplitude modulated with a 1 kHz sinewave. Where the frequency range is swept incrementally, the step size shall not exceed 1 % of the preceding frequency value.
- c. The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.

For Display and display output functions:

- a. The display quality evaluated by direct observation.
- b. For display output function evaluation, a suitable display device shall be connected. This device shall meet the immunity requirements for displays specified in this document. The screen size shall be typical for the display output. the diagonal screen size shall be at least 0,50 m.
- c. The display shall be observed under normal viewing conditions including viewing distance using a reduced ambient light level preferably in the range 15 lx to 20 lx. The viewing distance or settings of the video camera monitoring system shall be sufficient to provide visibility of the whole display. In the case of direct observation the selected viewing distance shall be recorded in the test report.


For Acoustic measurements:

- a. Apply an appropriate input signal to the EUT so that a sine wave (tone) at the frequency that will be used to modulate the applied disturbance (typically 1 kHz) is generated from the port under test at a level equal to the acoustic reference level.
- b. Record the resulting dB (SPL) level (or other appropriate dB unit) as the value of L_0 .
(BTL lab uses the software to take L_0 as the reference value and make it return to zero.)
- c. Change the input to the EUT so that the port under test is silent, or represents silence. This change shall not alter the terminating impedance at the EUT's input.
- d. Apply the RF disturbance to the applicable port of the EUT and record the resulting demodulated audio level in dB (SPL) (or other dB unit used in step d)) as the value of L_1 .
- e. Ensure that non-linear processing does not impact the measurements.
- f. Calculate the acoustic interference ratio using the following formula:
Acoustic interference ratio = $L_1 - L_0$.
(For step e-f, BTL lab proceeds the test with software and calculate Acoustic interference ratio = $L_1 - L_0$).

4.9.4 DEVIATION FROM TEST STANDARD


No deviation

4.9.5 TEST SETUP



For Audio output function

(1) Audio output port



The filter is the audio filter specified in G.6.1 and is typically incorporated into the audio meter. Additional filtering might be necessary to ensure that the RF disturbance signal does not interfere with the measurement.

4.9.6 TEST RESULTS


Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-10

Test Ports (Mode)	Freq.Range (MHz)	Field Strength	Modulation	Criteria	Results
AC mains power ports	0.15 - 10	3V	AM Modulated 1000Hz, 80%	A	A
	10 - 30	3V to 1V			
	30 - 80	1V			

For Audio output function

(1) For Audio output port:

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1_CDN M3



4.10 POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST (PFMF)

4.10.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-8
Required Performance	A
Frequency Range	50/60Hz
Field Strength	1 A/m
Observation Time	1 minute
Inductance Coil	Rectangular type, 1mx1m

4.10.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Magnetic Field test Generator	FCC	F-1000-4-8-G-125A	04032	Dec. 06, 2025
2	Magnetic Field immunity loop	Thermo KeyTek	F-1000-4-8/9 /10-L-1M	04024	Dec. 06, 2025

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.

4.10.3 TEST PROCEDURE

For TABLE-TOP equipment:

The equipment shall be subjected to the test magnetic field by using the induction coil of standard dimension (1 m x 1 m). The induction coil shall then be rotated by 90 degrees in order to expose the EUT to the test field with different orientations.


The other condition as following manner:

- a. The equipment cabinets shall be connected to the safety earth directly on the GRP via the earth terminal of the EUT.
- b. The cables supplied or recommended by the equipment manufacturer shall be used. 1 meter of all cables used shall be exposed to the magnetic field.

4.10.4 DEVIATION FROM TEST STANDARD

No deviation

4.10.5 TEST SETUP



4.10.6 TEST RESULTS

Test Voltage	AC 230V/50Hz
Test Mode	Mode 1-10

50Hz

Test Mode	Test Level	Antenna aspect	Duration	Criteria	Results
Enclosure	1 A/m	X	60s	A	A
Enclosure	1 A/m	Y	60s	A	A
Enclosure	1 A/m	Z	60s	A	A

60Hz

Test Mode	Test Level	Antenna aspect	Duration	Criteria	Results
Enclosure	1 A/m	X	60s	A	A
Enclosure	1 A/m	Y	60s	A	A
Enclosure	1 A/m	Z	60s	A	A

4.11 VOLTAGE DIPS, SHORT INTERRUPTIONS AND VOLTAGE VARIATIONS IMMUNITY TEST (DIPS)

4.11.1 TEST SPECIFICATION

Basic Standard	IEC 61000-4-11
Required Performance	Voltage dips: B (For <5% residual voltage, dips) C (For 70% residual voltage, dips) C (For <5% residual voltage, Interruptions)
Interval between Event	Ten seconds
Phase Angle	0°/180°
Test Cycle	3 times

4.11.2 MEASUREMENT INSTRUMENTS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Calibrated until
1	Cycle Sag Simulator	Prima	DRP61011TA	PR19076452	May 31, 2025

Remark: "N/A" denotes no model name, no serial No. or no calibration specified.

All calibration period of equipment list is one year.


4.11.3 TEST PROCEDURE

The EUT shall be tested for each selected combination of test levels and duration with a sequence of three dips/interruptions with intervals of 10 s minimum (between each test event). Each representative mode of operation shall be tested. Abrupt changes in supply voltage shall occur at zero crossings of the voltage waveform.

4.11.4 DEVIATION FROM TEST STANDARD

No deviation

4.11.5 TEST SETUP



4.11.6 TEST RESULTS

Test Voltage	AC 100V/50Hz, AC 230V/50Hz, AC 240V/50Hz
Test Mode	Mode 1-10



AC 100V/50Hz				
Item	Residual Voltage	Cycle	Criteria	Results
Voltage dips	<5%	0.5	B	A
Voltage dips	70%	25	C	C
Voltage Interruption	<5%	250	C	C

AC 230V/50Hz				
Item	Residual Voltage	Cycle	Criteria	Results
Voltage dips	<5%	0.5	B	A
Voltage dips	70%	25	C	A
Voltage Interruption	<5%	250	C	C



AC 240V/50Hz				
Item	Residual Voltage	Cycle	Criteria	Results
Voltage dips	<5%	0.5	B	A
Voltage dips	70%	25	C	A
Voltage Interruption	<5%	250	C	C

5. EUT TEST PHOTO

Radiated emissions up to 1 GHz



Radiated emissions above 1 GHz



Conducted emissions AC mains power port



Harmonic current




Voltage fluctuations (Flicker)




Electrostatic discharge immunity




Radiated, radio-frequency, electromagnetic field immunity – Up to 1GHz




Radiated, radio-frequency, electromagnetic field immunity – Above 1GHz



Electrical fast transient/burst immunity - AC



Surge immunity - AC**Immunity to conducted disturbances, induced by radio-frequency fields - AC**

Power frequency magnetic field immunity



Voltage dips, short interruptions and voltage variations immunity



End of Test Report